NEW PALACE DIVISION, MYSORE.

Tender Notice.

Sealed tenders or estimate will be received in the Office of the Architectural Executive Engineer, New Palace Division, at Nazarabad in the City of Mysore on or before the 11th July 1918, for all labour and materials required for the erection of basement and superstructure (as per items and quantities noted in the schedule hereto appended) of the New Palace to be constructed near Lalitadri Hill at Mysore.

The time allowed for the completion of work will be 30 calendar months from the date of issue of notice of acceptance of contract for the first eight months of which a fair proportion of the bricks and other materials required for the work should be collected at site. The rate of monthly progress in the collection of bricks, etc., for this period and the actual construction after its commencement should be specified in the tender in the form hereto annexed.

The earnest money required will be rupees three thousand, which must accompany the tender either in cash, Government Paper or a fixed deposit receipt in the Banks of Mysore or Madras (which should be endorsed payable to the Executive Engineer). This amount will be returned if the tender is not accepted, while, the same will be kept in deposit as a guarantee fund for the due fulfilment of the conditions as laid down in the tender of successful tenderers and which will be forfeited to Government if the terms of the tender are not properly carried out.

No tender, shall be withdrawn pending the award.

Each tender shall contain the name and place of residence of the person submitting the same, with the names of works he is at present engaged stating also the names of large buildings he has recently completed.

The successful tenderer must be prepared to deposit in cash or other security at least 5 per cent of the total value of the work entrusted to him amounting to nearly Rs. 12,000 and this amount will only be returned to him after the work referred to in this contract is completed in all respects and finally paid for.

For further particulars regarding the nature and extent of the work required or of the materials to be supplied tenderers are referred to the plans, estimates, and specifications which will be on file at the office of the Executive Engineer.

Bidders are requested to submit their tender upon the blank form that can be obtained on application at the office of the Executive Engineer.

Schedule of rates accompanying the tender.

No.	Items of work	Per	Quantity	Rate
				Rs. a. p.
1	Wirecut-brick Masonry in mortar for basement	C. ft.	99,600	
2	½" thick cement plaster (1 : 4)	100 S. ft.	10,244	
3	Stone slabs 6" thick	C. ft.	5,575	
4	Dressing do one line	S. ft.		
5	Do two lines			
6	Do three lines			
7	Jack Arched terrace 4 to 10 ft. span and 9" thick at the crown (2 courses brick on edge, one flat and three layers flat tiles)	100 S. ft.	22,268	
8	Madras terrace 7" thick (for ground floor one course on edge one flat and 3" concrete).		25,500	
9	Madras terrace 9" thick (one brick on edge, one flat, 3" concrete plus 3 courses flat tiles)		38,538	
10	Wirecut-brick in mortar for superstructure ground floor	C. ft.	179,002	
11	Do do first floor ...		142,307	
12	Circular stone columns of diameter carrying from 12" to 2' 0" ..	C. ft.	33,057	
13	Cement concrete (1 : 2½ : 4)		9,907	
14	Do (1 : 3 : 5)		3,500	
15	Ordinary line plaster in three coats finely finished	100 S. ft.	165,697	

S. H. LAKSHMINARASAPPA,
Architectural Executive Engineer.

KRISHNARAJASAGARA WORKS.

Abstract Notification.

The attention of the public is invited to the publication dated 20th June 1918, on page 561, Part IV of the *Mysore Gazette*, wherein tenders for the supply of charcoal required for use on the North Bank of Krishnarajasagara Works for the period commencing from 1st August 1918 to 31st August 1919, is called for.

B. B. GARUDACHARYA,
Superintending Engineer.